

CAPITAL CONSTRUCTION DEPARTMENT 700 ANDOVER PARK WEST - SUITE C * SEATTLE, WA 98188

ADDENDUM:	3		TODAY'S DATE:	11/08/24
PROJECT NAME:	WESTMINSTER :	MANOR ENV	ELOPE & ROO	F
CONTACT / TITLE:	CARL FRANKEL PROJECT MANAGER			
PHONE / EMAIL:	206-574-1249 Carlf@kcha.org			
This Addendum is use	ed to Identify Items i ☑ BID	in the Original D □ RFQ	ocuments with A	ction as Follows:
☑ CLARIFY	☑ CHANGE □	DELETE .	ADD	SUBSTITUTE
Page(s) Total for this Addenda including this page. 1. CLARIFY: The Table of Contents for Division 1 General Requirements has Section 017329				
	atching) listed twice. T and is part of the bid d	_	Patching section is i	ncluded in the
2. CLARIFY: In	the Scope of Work &	Specifications Ta	ble of Contents (pa	ge 191 in the bid

3. CLARIFY: A request for a substitute TPO material called Mule Hide was made during the open question period. This request is rejected. Contractors are to bid on specified products in

documents) the Thermoplastic Polyolefin Roofing is listed under Section 07 54 00. The TPO

4. CLARIFY: KCHA Capital Construction does not publish an engineer's estimate.

Roofing specification can be found in Section 07 54 23.

the bid documents.

- 5. CLARIFY: Roof demolition to include (but not limited to) removal of existing roofing, cover board, insulation, flashing, and concrete topping.
- 6. ADD: Contractor is to assume that the existing concrete topping layer at the roof is to be removed and is an average of 4" in depth. Assume that the existing coverboard and rigid insulation is to be removed at the roof and is an average of 2" in depth.
- 7. CHANGE: KCHA weatherization is adding new ventilation in each unit. As a Unit Price, Contractor to add ¼" mineral-wool insulation and 2'x4'x3/4" CDX plywood blocking at each unit to replace the 1" exterior insulation at that location to mount vents. These blocks will be located behind the fiber cement panels on either side of the sliding glass doors. Exact location

TBD. See Exhibit V for Unit Pricing form and include with bid. For bidding purposes, pricing as a <u>PER UNIT</u> price (One block.)					
	END OF ADDENDUM #3				



SCOPE OF WORK & TECHNICAL SPECIFICATIONS

SCOPE OF WORK

DIVISION 1 – GENERAL REQUIREMENTS

01 10 00	Summary
01 73 29	Cutting & Patching
01 26 00	Contract Modification Procedures
01 29 00	Payment Procedures
01 31 00	Project Management & Coordination
01 32 00	Construction Progress Documentation
01 33 00	Submittal Procedures
01 40 00	Quality Requirements
01 50 00	Temporary Facilities & Controls
01 60 00	Product Requirements
01 73 00	Execution
01 73 29	Cutting and Patching
01 74 19	Construction Waste Management
01 77 00	Closeout
01 78 23	Operation and Maintenance Data
01 78 39	Project Record Documents
*****	KCHA Pay Application Form (sample)
*****	KCHA Substitute Request Form (sample)

DIVISION 2 EXISTING CONDITIONS

02 41 00 DEMOLITION

DIVISION 5 METALS

05 50 00 METAL FABRICATIONS

DIVISION 6 WOOD AND PLASTICS

06 10 00 ROUGH CARPENTRY

DIVISION 7 THERMAL AND MOISTURE PROTECTION

07/14/00	FLUID-APPLIED WATERPROOFING
07 21 00	BUILDING INSULATION
07 25 00	WEATHER BARRIERS
07 46 46	FIBER-CEMENT SIDING
075423 07 54 00	THERMOPLASTIC-POLYOLEFIN ROOFING
07 62 00	SHEET METAL FLASHING AND TRIM
07 92 00	JOINT SEALANTS



KCHA – WESTMINSTER MANOR ENVELOPE & ROOF

CAPITAL CONSTRUCTION DEPARTMENT

DIVISION 8 OPENINGS

08 53 13	VINYL WINDOWS & SLIDING GLASS DOORS
08 71 00	DOOR HARDWARE
08 91 00	LOUVERS

DIVISION 9 FINISHES

09 21 16	GYPSUM BOARD ASSEMBLIES
09 91 13	EXTERIOR PAINTING
09 91 23	INTERIOR PAINTING

DIVISION 12 FURNISHINGS

12 21 13	HORIZONTAL LOUVER BLINDS
12 21 16	VERTICAL LOUVER BLINDS

DIVISION 21 FIRE SUPPRESSION

21 20 00 PIPE ENCLOSURE SYSTEM

END OF SECTION

Drawings & Specifications Page 3 of 5 KCHA / 08-05-21

Exhibit V

<u>nsulati</u>		*
Α.	Materials, including all applicable Taxes	\$
В.	Labor	\$
C.	O & P, including all applicable Fees	\$
TOTAI	L BID AMOUNT: (all costs inclusive – A, B, and C)	
		And No/100 Dollars

